

CENTRALIZATOR

STR LAHOVARY

Nr. crt.	Cod deviz	Denumirea lucrarii	Valoare		
			fara T.V.A.	T.V.A.	cu T.V.A.
1	SAR114	Borduri prefabricate din beton 20 x 25 cm 245 ml			
2	SAR111	Paviment granit 290 ml			
3	SAR110	Reparatie strat de fundatie din beton, 10 cm gros. 774 mp 50 % din S = 387 mp			
4	SAR112	Strat de uzura din beton asfaltic BA8, 4 cm gros 774 mp			
5	SAR115	Reparatie strat de fundatie din beton, 20 cm gros. 5% din 1584 =79.20 mp			
6	SAR116	Strat de legatura din beton asfaltic BAD20, 3 cm grosime - 792 mp ;50% din 1584 mp			
7	SAR117	Strat de uzura din beton asfaltic BA16, 5 cm gros 1584 mp			
8	SAR118	Aducerea la cota a caminelor existente 17 buc			
9	SAR113	Desfacere si montare bordura Granit 100 ml			
10	SAR119	Aducerea la cota a gurilor de scurgere existente 7 buc			
	TOTAL		0.00	0.00	0.00

1	ROS888	Demontat si montat bordura scuar str Brailei			
---	--------	--	--	--	--



Formularul F3

Obiectivul: 0002 538976288 Lucrari de intretinere drum

Obiectul: 0003 45000000 P

Lista cu cantitatile de lucrari

Deviz oferta SAR110 REPARATII STRAT DE FUNDATIE DIN BETON 10 CM GROSIME LA TROTUARE - ANALIZA DE PRET
(LEI/100 MP)

Categoria de lucrari: 8300

Nr. Capitol de lucr. crt. sau Subcapitol(norma comasata) Denumire	UM	CANTITATEA	PU a)Material b)Manopera c)Utilaj d)Transport (RON /UM)	MATERIAL (col.3x col.4a) (RON)	MANOPERA (col.3x col.4b) (RON)	UTILAJ (col.3x col.4c) (RON)	TRANSPORT (col.3x col.4d) (RON)	TOTAL (col.5+ 6+7+8) (RON)
--	----	------------	---	---	---	---	--	---------------------------------------

Sectiunea tehnica				Sectiunea financiara					
0	1	2	3	4	5	6	7	8	9
001	DG06A1	[18] M.C.	3.000						
Spargerea si desf.bet.									

002 RPCT09F1 [21] M.C. 10.000
DEMOLAREA ELEMENTELOR DIN BETON

003 DA15A1 [49] MP. 100.000
Fund bet ciment 10 cm gr la trot,alei pe
pat exist

003 2100945 M.C. 10.100
Beton de ciment B 150

004 TRI1AH03E1 [10] TONA 29.050
Inc.mat cu buldoexcavatorul

005 TRA01A10 TONA 29.050
Transp.rutier pamant,moloz, mat. cu
auto, d=10 km

006 DF24A1 [2] BUC. 1.000
Semnalizare rutiera lucrari

Cheltuieli directe din articole:

GREUTATE MATERIALE MANOPERA UTILAJ TRANSPORT TOTAL

Din care:

Valoare aferenta utilaje termice =

=====

Valoare aferenta utilaje electrice =

Detaliere transporturi:

-Articole TRA

Alte cheltuieli directe:

-Contributie asiguratorie pentru munca

Total cheltuieli directe:

GREUTATE	MATERIALE	MANOPERA	UTILAJ	TRANSPORT	TOTAL
----------	-----------	----------	--------	-----------	-------

Cheltuieli indirecte:	0.083
-----------------------	-------

Profit:	0.050
---------	-------

TOTAL GENERAL DEVIZ:

TVA


TOTAL cu TVA

SEB SECTIE IRU

ING. URSACHEL DANIELA

INTOCMIT

ING. SPULBER VIOLETA MIOARA



Lista consumurilor de resurse materiale (cantitati totale)

Lucrarea: Lucrari de intretinere drum

Devize: SAR110

Nr. Crt.	Denumirea resursei materiale	U.M.	Consumuri cuprinse in oferta	Pret unitar exclusiv TVA RON	Valoare exclusiv TVA RON	Furnizor	Greutate (tone)
0	1	2	3	4	5	6	7
1	2100945 Beton de ciment B 150	M.C.	10.10				24.846
2	2200525 Nisip sortat nesp. 0,0-7,0 mm	M.C.	1.60				2.720
3	6202806 APA INDUSTRIALA PENTRU LUCRARI DRUMURI SI TERASAMENTE IN CISTERNE	M.C.	1.20				1.200
T O T A L					RON		28.766
					EURO		

Ofertant



Lista consumurilor cu mana de lucru (cantitati totale)

Lucrarea: Lucrari de intretinere drum

Devize: SAR110

Nr. Crt.	Denumirea meseriei	Consumuri (om-ore) cu manopera directa	Tarif mediu RON/ora	Valoare(exclusiv TVA) RON (2 x 3)	Procent 100%
0	1	2	3	4	5
1	102 Betonist	28.398			
2	199 Muncitor deserv.c-tii.montaj	73.654			
	TOTAL	102.052	RON		
			EURO		

Ofertant



h

Lista consumurilor de ore de functionare a utilajelor de constructii (cantitati totale)

Lucrarea: Lucrari de intretinere drum

Devize: SAR110

Nr. Crt.	Denumirea utilajului de constructii	Consumuri ore de functionare	Tarif orar RON/ ora functionare	Valoare (exclusiv TVA) RON (2 x 3)
0	1	2	3	4
1	1164 Buldoexcavator mic	3.500		
2	1173 BULDOEXCAVATOR CU INCARCATOR	3.262		
3	3918 Motocompresor Ingersoll	2.400		
4	5603 Autocisterna	0.100		
TOTAL		9.262	RON	
			EURO	

Ofertant



Formularul F3

Obiectivul: 0002 538976288 Lucrari de intretinere drum

Obiectul: 0003 45000000 P

Lista cu cantitatile de lucrari

Deviz oferta SAR111 PAVIMENT GRANIT

Categoria de lucrari: 8300

Nr. Capitol de lucr. crt.	UM	CANTITATEA	PU	MATERIAL	MANOPERA	UTILAJ	TRANSPORT	TOTAL
sau			a)Material	(col.3x	(col.3x	(col.3x	(col.3x	(col.5+
Subcapitol(norma comasata)			b)Manopera	col.4a)	col.4b)	col.4c)	col.4d)	6+7+8)
Denumire			c)Utilaj					
			d)Transport					
			(RON /UM)	(RON)	(RON)	(RON)	(RON)	(RON)

Sectiunea tehnica				Sectiunea financiara					
0	1	2	3	4	5	6	7	8	9

001 TSE06A1 100 MP. 2.900
PREGATIREA PLATF.PAM.PT.STRAT IZOLATOR
SI REPARTITIE DIN NISIP SAU BALAST EXEC.
IN PAM.NECOEZ.

002 DA06A1 [59] M.C. 29.000
STRAT AGREG NAT(BALAST)CILINDR CU FUNCT
REZIST FILTRANT IZOL AERISIRE ANTCAPI
ASTERNERE MANUAL

003 DA15B1 [28] MP. 290.000
FUND BETON CIMENT 10 CM GROS LA TROT
ALEI PIETONI CICLISTI EXEC PE SUBSRAT
NISIP 5 CM GROS

004 2100995 M.C. 29.000
Beton de ciment B 400

005 TRA01A10 TONA 64.630
Transp.rutier pamant,moloz, mat. cu
auto, d=10 km

006 DE14A1 MP. 290.000
PLACI PREF BETON LA TROT DE FUND BETON
10 CM GROS PRIN INTERMEDIUL A 2 CM MORT
CIM INCL ROSTUIRE

007 2101183 M.C. 5.800
Mortar de zidarie M 100

008 TRA01A10 TONA 28.230
Transp.rutier pamant,moloz, mat. cu
auto, d=10 km

008 7600698 MP. 290.000
PLACI DE GRANIT 60 X 30 X4

Cheltuieli directe din articole:

GREUTATE	MATERIALE	MANOPERA	UTILAJ	TRANSPORT	TOTAL
----------	-----------	----------	--------	-----------	-------

Din care:

Valoare aferenta utilaje termice =

Valoare aferenta utilaje electrice =

Detaliiere transporturi:

-Articole TRA

Alte cheltuieli directe:

-Contributie asiguratorie pentru munca

Total cheltuieli directe:

GREUTATE	MATERIALE	MANOPERA	UTILAJ	TRANSPORT	TOTAL
----------	-----------	----------	--------	-----------	-------

Cheltuieli indirecte: 0.083

Profit: 0.050

TOTAL GENERAL DEVIZ:

TVA

TOTAL cu TVA

SEF SECTIE IRU
ING. URSACHEL DANIELA

INTOCMIT
ING. SPULBER VIOLETA MIOARA


Lista consumurilor de resurse materiale (cantitati totale)

Lucrarea: Lucrari de intretinere drum

Dezice: SAR111

Nr. Crt.	Denumirea resursei materiale	U.M.	Consumuri cuprinse in oferta	Pret unitar exclusiv TVA RON	Valoare exclusiv TVA RON	Furnizor	Greutate (tone)
0	1	2	3	4	5	6	7
1	2100440 Ciment Portland cu adaos PA 35	KG	464.00				0.469
2	2100995 Beton de ciment B 400	M.C.	29.00				76.850
3	2101183 Mortar de zidarie M 100	M.C.	5.80				14.036
4	2200393 Balast nesp.de rau 0-70 mm	M.C.	38.02				64.632
5	2200513 Nisip sort nesp. 0,0-3,0 mm	M.C.	1.45				2.465
6	2200525 Nisip sortat nesp. 0,0-7,0 mm	M.C.	23.20				39.440
7	6202806 APA INDUSTRIALA PENTRU LUCRARI DRUMURI SI TERASAMENTE IN CISTERNE	M.C.	13.11				13.108
8	6202818 Apa ind.pt.mortare,betoane	M.C.	0.58				0.580
9	7600698 PLACI DE GRANIT 60 X 30 X4	MP.	290.00				0.232
TOTAL					RON		211.812
					EURO		

Ofertant



8

Lista consumurilor cu mana de lucru (cantitati totale)

Lucrarea: Lucrari de intretinere drum

Devize: SAR111

Nr. Crt.	Denumirea meseriei	Consumuri (om-ore) cu manopera directa	Tarif mediu RON/ora	Valoare(exclusiv TVA) RON (2 x 3)	Procent 100%
0	1	2	3	4	5
1	102 Betonist	82.354			
2	113 Finisor teras.	15.773			
3	128 Pavator	437.094			
4	199 Muncitor deserv.c-tii.mont.	23.183			
TOTAL		558.404	RON		
			EURO		

Ofertant




Lista consumurilor de ore de functionare a utilajelor de constructii (cantitati totale)

Lucrarea: Lucrari de intretinere drum

Devize: SAR111

Nr. Crt.	Denumirea utilajului de constructii	Consumuri ore de functionare	Tarif orar RON/ ora functionare	Valoare (exclusiv TVA) RON (2 x 3)
0	1	2	3	4
1	4004 Cilindru compactor	3.480		
2	4005 Cilindru compactor	4.437		
3	5603 Autocisterna	0.957		
T O T A L		8.874	RON	
			EURO	

Ofertant



Formularul F3

Obiectivul: 0002 538976288 Lucrari de intretinere drum

Obiectul: 0003 45000000 P

Lista cu cantitatile de lucrari

Deviz oferta SAR112 IMBRACAMINTE ASFALTICA DIN BA8 - 4 CM GROSIME - ANALIZA DE PRET (LEI/100 MP)

Categoria de lucrari: 8300

Nr. Capitol de lucr. crt.	UM	CANTITATEA	PU	MATERIAL	MANOPERA	UTILAJ	TRANSPORT	TOTAL
sau			a)Material	(col.3x	(col.3x	(col.3x	(col.3x	(col.5+
Subcapitol(norma comasata)			b)Manopera	col.4a)	col.4b)	col.4c)	col.4d)	6+7+8)
Denumire			c)Utilaj					
			d)Transport					
			(RON /UM)	(RON)	(RON)	(RON)	(RON)	(RON)

Sectiunea tehnica				Sectiunea financiara					
0	1	2	3	4	5	6	7	8	9

001 DB01A1 [3] MP. 100.000
Curatirea man. a suprafetelor

002 DB02D1 [13] 100 MP. 1.000
Amorsare supraf.

003 DB16D1 MP. 100.000
IMBRAC BET ASF CU AGREGATE MARUNTE
EXECUTATA LA CALD, IN GROSIME DE 4,0 CM,
CU ASTERNERE MANUALA

004 AUT1173 ORA 1.410
BULDOEXCAVATOR CU INCARCATOR

Cheltuieli directe din articole:

GREUTATE	MATERIALE	MANOPERA	UTILAJ	TRANSPORT	TOTAL
----------	-----------	----------	--------	-----------	-------

Alte cheltuieli directe:

-Contributie asiguratorie pentru munca

Total cheltuieli directe:

GREUTATE	MATERIALE	MANOPERA	UTILAJ	TRANSPORT	TOTAL
----------	-----------	----------	--------	-----------	-------

Cheltuieli indirecte: 0.083

Profit: 0.050

TOTAL GENERAL DEVIZ:

TVA
TOTAL cu TVA

SEF SECTIE IBU
ING. URSACHEL DANIELA

INTOCMIT
ING. SPULBER VIOLETA MIHARA



Lista consumurilor de resurse materiale (cantitati totale)

Lucrarea: Lucrari de intretinere drum

Dezice: SAR112

Nr. Crt.	Denumirea resursei materiale	U.M.	Consumuri cuprinse in oferta	Pret unitar exclusiv TVA RON	Valoare exclusiv TVA RON	Furnizor	Greutate (tone)
0	1	2	3	4	5	6	7
1	2590017 Beton asfaltic BA8	TONA	9.40				9.400
2	2600323 Emulsie bitum cationica	KG	45.50				0.050
3	3421097 OTEL PATRAT LAMINAT LA CALD S 334 OL37-1N LT= 30	KG	1.10				0.001
T O T A L				RON			9.451
				EURO			

Ofertant



Lista consumurilor cu mana de lucru (cantitati totale)

Lucrarea: Lucrari de intretinere drum

Devize: SAR112

Nr. Crt.	Denumirea meseriei	Consumuri (om-ore) cu manopera directa	Tarif mediu RON/ora	Valoare(exclusiv TVA) RON (2 x 3)	Procent 100%
0	1	2	3	4	5
1	101 Asfaltator	13.603			
2	199 Muncitor deserv.c-tii.montaj	15.000			
	TOTAL	28.603	RON		
			EURO		

Ofertant

Lista consumurilor de ore de functionare a utilajelor de constructii (cantitati totale)

Lucrarea: Lucrari de intretinere drum

Dezize: SAR112

Nr. Crt.	Denumirea utilajului de constructii	Consumuri ore de functionare	Tarif orar RON/ ora functionare	Valoare (exclusiv TVA) RON (2 x 3)
0	1	2	3	4
1	1173 BULDOEXCAVATOR CU INCARCATOR	1.410		
2	4005 Cilindru compactor	1.140		
TOTAL		2.550	RON	
			EURO	

Ofertant



Formularul F3

Obiectivul: 0002 538976288 Lucrari de intretinere drum

Obiectul: 0003 45000000 P

Lista cu cantitatile de lucrari

Deviz oferta SAR113 ANALIZA DE PRET DESFACERE BORDURA MARE DE GRANIT

Categoriza de lucrari: 8300

Nr. crt.	Capitol de lucr. sau Subcapitol (norma comasata)	UM	CANTITATEA	PU	MATERIAL	MANOPERA	UTILAJ	TRANSPORT	TOTAL
	Denumire			a)Material b)Manopera c)Utilaj d)Transport (RON /UM)	(col.3x col.4a) (RON)	(col.3x col.4b) (RON)	(col.3x col.4c) (RON)	(col.3x col.4d) (RON)	(col.5+ 6+7+8) (RON)

Sectiunea tehnica				Sectiunea financiara					
0	1	2	3	4	5	6	7	8	9

001 DG04B1 M 100.000
DES.DE BORDURI DIN PIATRA SAU DE BETON
ORICE DIM. ASEZATA PE BETON

002 DG06B1 [24] M.C. 2.250
SPARGEREA SI DESFACERE BETON CU
BULDOEXCAVATORUL MIC

003 DE10A1 [32] M 100.000
MONTAT BORDURI 20X25X50 DE GRANIT

003 2100945 M.C. 4.500
Beton de ciment B 150

004 TRB05A13 [2] TONA 13.000
Transport mat. p.p.d.

005 TRI1AH03E1 [53] TONA 18.400
INCARCARE MAT CU BULDOEXCAVATORUL T

006 TRA01A10 TONA 18.400
Transp.rutier pamant,moloz, mat. cu
auto, d=10 km

Cheltuieli directe din articole:

GREUTATE MATERIALE MANOPERA UTILAJ TRANSPORT TOTAL

Din care:

Valoare aferenta utilaje termice =

Valoare aferenta utilaje electrice =

Detaliere transporturi:

-Articole TRA

Alte cheltuieli directe:

-Contributie asiguratorie pentru munca

Total cheltuieli directe:

GREUTATE	MATERIALE	MANOPERA	UTILAJ	TRANSPORT	TOTAL
----------	-----------	----------	--------	-----------	-------

Cheltuieli indirecte:	0.083				
-----------------------	-------	--	--	--	--

Profit:	0.050				
---------	-------	--	--	--	--

TOTAL GENERAL DEVIZ:

TVA

TOTAL cu TVA

SEF SECTIE IRU
ING. URSACHEL DANIELA

INTOCMIT
ING. SPULBER VIOLETA MIOARA

14

Lista consumurilor de resurse materiale (cantitati totale)

Lucrarea: Lucrari de intretinere drum

Dezice: SAR113

Nr. Crt.	Denumirea resursei materiale	U.M.	Consumuri cuprinse in oferta	Pret unitar exclusiv TVA RON	Valoare exclusiv TVA RON	Furnizor	Greutate (tone)
0	1	2	3	4	5	6	7
1	2100024 Ciment Portland P 40	KG	292.00				0.295
2	2100945 Beton de ciment B 150	M.C.	4.50				11.070
3	2200513 Nisip sort nesp. 0,0-3,0 mm	M.C.	0.80				1.360
4	6202818 Apa ind.pt.mortare,betoane	M.C.	0.60				0.600
5	7650050 BORDURA DE GRANIT 200 X 250 X 500	BUC.	200.00				0.100
TOTAL					RON		13.425
					EURO		

Ofertant


18


Lista consumurilor cu mana de lucru (cantitati totale)

Lucrarea: Lucrari de intretinere drum

Devize: SAR113

Nr. Crt.	Denumirea meseriei	Consumuri (om-ore) cu manopera directa	Tarif mediu RON/ora	Valoare(exclusiv TVA) RON (2 x 3)	Procent 100%
0	1	2	3	4	5
1	128 Pavator	44.087			
2	196 Sapator	14.038			
3	199 Muncitor deserv.c-tii.mont.	65.684			
4	3197 Muncitor inc.-desc.mat.	2.760			
T O T A L		126.569	RON		
			EURO		

Ofertant




Lista consumurilor de ore de functionare a utilajelor de constructii (cantitati totale)

Lucrarea: Lucrari de intretinere drum

Devize: SAR113

Nr. / Crt.	Denumirea utilajului de constructii	Consumuri ore de functionare	Tarif orar RON/ ora functionare	Valoare (exclusiv TVA) RON (2 x 3)
0	1	2	3	4
1	1164 Buldoexcavator mic	7.409		
	TOTAL	7.409	RON	
			EURO	

Ofertant



Formularul F3

Obiectivul: 0002 538976288 Lucrari de intretinere drum

Obiectul: 0003 45000000 P

Lista cu cantitatile de lucrari

Deviz oferta SAR114 DESFACERE BORDURA MARE 20X25X50CM SI MONTARE BORDURA MARE 20X25X50 CM - LEI/ML

Categoriza de lucrari: 8300

Nr. Capitol de lucr. crt. sau Subcapitol (norma comasata) Denumire	UM	CANTITATEA	PU a)Material b)Manopera c)Utilaj d)Transport (RON /UM)	MATERIAL (col.3x col.4a) (RON)	MANOPERA (col.3x col.4b) (RON)	UTILAJ (col.3x col.4c) (RON)	TRANSPORT (col.3x col.4d) (RON)	TOTAL (col.5+ 6+7+8) (RON)
--	----	------------	---	---	---	---	--	---------------------------------------

Sectiunea tehnica				Sectiunea financiara					
0	1	2	3	4	5	6	7	8	9

001 DG04B1 M 100.000
DES.DE BORDURI DIN PIATRA SAU DE BETON
ORICE DIM. ASEZATA PE BETON

002 DG06B1 [24] M.C. 2.250
SPARGEREA SI DESFACERE BETON CU
BULDOEXCAVATORUL MIC

003 DE10A1 [8] M 100.000
Borduri mari pref bet pt trot 20X25 cm,
cu L=0,50 m

003 2100945 M.C. 4.500
Beton de ciment B 150

004 TRB05A13 TONA 11.000
Transport mat. p.p.d.

005 TRI1AH03E1 [31] TONA 15.950
INCARCARE MATERIALE IN AUTO CU
BULDOEXCAVATORUL

006 TRA01A10 TONA 15.950
Transp.rutier pamant,moloz, mat. cu
auto, d=10 km

Cheltuieli directe din articole:

GREUTATE MATERIALE MANOPERA UTILAJ TRANSPORT TOTAL

Din care:

Valoare aferenta utilaje termice =

Valoare aferenta utilaje electrice =

Detaliere transporturi:

-Articole TRA

Alte cheltuieli directe:

-Contributie asiguratorie pentru munca

Total cheltuieli directe:

GREUTATE	MATERIALE	MANOPERA	UTILAJ	TRANSPORT	TOTAL
----------	-----------	----------	--------	-----------	-------

Cheltuieli indirecte:	0.083
-----------------------	-------

Profit:	0.050
---------	-------

TOTAL GENERAL DEVIZ:

TVA

TOTAL cu TVA

SEF SECTIE IRU
ING. URSACHEL DANIELA



INTOCMIT,
ING. SPULBER VIOLETA MIOANA




Lista consumurilor de resurse materiale (cantitati totale)

Lucrarea: Lucrari de intretinere drum

Devize: SAR114

Nr. Denumirea resursei materiale U.M. Consumuri Pret unitar Valoare Furnizor Greutate							
Crt. cuprinse exclusiv TVA exclusiv TVA (tone)							
0 1 2 3 4 5 6 7							
			in oferta	RON	RON		
1	2100024 Ciment Portland P 40	KG	292.00				0.295
2	2100945 Beton de ciment B 150	M.C.	4.50				11.070
3	2200513 Nisip sort nesp. 0,0-3,0 mm	M.C.	0.80				1.360
4	6202818 Apa ind.pt.mortare,betoane	M.C.	0.60				0.600
5	7503019 Borduri mari 500x200x250mm	BUC.	200.00				12.500
T O T A L				RON			25.825
				EURO			

Ofertant



Lista consumurilor cu mana de lucru (cantitati totale)

Lucrarea: Lucrari de intretinere drum

Dezize: SAR114

Nr. / Crt.	Denumirea meseriei	Consumuri (om-ore) cu manopera directa	Tarif mediu RON/ora	Valoare(exclusiv TVA) RON (2 x 3)	Procent 100%
0	1	2	3	4	5
1	128 Pavator	44.087			
2	196 Sapator	14.038			
3	199 Muncitor deserv.c-tii.mont.	61.964			
4	3197 Muncitor inc.-desc.mat.	2.392			
T O T A L		122.481	RON		
			EURO		

Ofertant



Lista consumurilor de ore de functionare a utilajelor de constructii (cantitati totale)

Lucrarea: Lucrari de intretinere drum

Devize: SAR114

Nr. / Crt.	Denumirea utilajului de constructii	Consumuri ore de functionare	Tarif orar RON/ ora functionare	Valoare (exclusiv TVA) RON (2 x 3)
0	1	2	3	4
1	1164 Buldoexcavator mic	1.125		
2	1173 BULDOEXCAVATOR CU INCARCATOR	2.871		
TOTAL		3.996	RON	
			EURO	

Ofertant

