

Formularul F3

Obiectivul: 0002 538976288 Lucrari de intretinere drum

Obiectul: 0003 45000000 P

Lista cu cantitatile de lucrari

Deviz oferta SAR119 RIDICARE LA COTA GURI DE SCURGERE (GEIGHERE) - ANALIZA DE PRET (LEI/BUC)

Categoría de lucrari: 8300

Nr. Capitol de lucr. crt. sau Subcapitol(norma comasata) Denumire	UM	CANTITATEA	PU a)Material b)Manopera c)Utilaj d)Transport (RON /UM)	MATERIAL (col.3x col.4a) (RON)	MANOPERA (col.3x col.4b) (RON)	UTILAJ (col.3x col.4c) (RON)	TRANSPORT (col.3x col.4d) (RON)	TOTAL (col.5+ 6+7+8) (RON)
---	----	------------	---	---	---	---	--	---------------------------------------

Sectiunea tehnica				Sectiunea financiara					
0	1	2	3	4	5	6	7	8	9
001	DC04B1	M	4.400						
TAIEREA CU MAS.CU DISC DIAMANT ROST CONTRACTIE SI DILATATIE BETON UZURA LA DRUMURI									
001	DG06A1	[13] M.C.	0.238						
Sparg. si desf. beton									
002	RP113A1	[1] BUC.	1.000						
Ridic.la cota guri de scurgere									
003	DC05C1	[9] MP.	0.950						
Imbrac bet cim B400 gr. 20 cm									
003	2100995	M.C.	0.191						
Beton de ciment B 400									
004	TRI1AH03E1	[31] TONA	0.524						
INCARCARE MATERIALE IN AUTO CU BULDOEXCAVATORUL									
005	TRB01A11	[1] TONA	1.095						
Transport mat. cu roaba									
006	TRA01A10	TONA	0.524						
Transp.rutier pamant,moloz, mat. cu auto, d=10 km									

007 DF24A1 [2] BUC. 1.000
Semnalizare rutiera lucrari

Cheltuieli directe din articole:

GREUTATE	MATERIALE	MANOPERA	UTILAJ	TRANSPORT	TOTAL
----------	-----------	----------	--------	-----------	-------

Din care:

Valoare aferenta utilaje termice =

Valoare aferenta utilaje electrice =

Detaliiere transporturi:

-Articole TRA

Alte cheltuieli directe:

-Contributie asiguratorie pentru munca

Total cheltuieli directe:

GREUTATE	MATERIALE	MANOPERA	UTILAJ	TRANSPORT	TOTAL
----------	-----------	----------	--------	-----------	-------

Cheltuieli indirecte: 0.083

Profit: 0.050

TOTAL GENERAL DEVIZ:

TVA

TOTAL cu TVA

SEF SECTIE IRU
ING. URSACHEL DANIELA

INTOCMIT
ING. SPULBER VIOLETA MIOARA

47

Lista consumurilor de resurse materiale (cantitati totale)

Lucrarea: Lucrari de intretinere drum

Devize: SAR119

Nr. Crt.	Denumirea resursei materiale	U.M.	Consumuri cuprinse in oferta	Pret unitar exclusiv TVA RON	Valoare exclusiv TVA RON	Furnizor	Greutate (tone)
0	1	2	3	4	5	6	7
1	2100995 Beton de ciment B 400	M.C.	0.19				0.506
2	2200525 Nisip sortat nesp. 0,0-7,0 mm	M.C.	0.03				0.048
3	6002737 DISC ARMAT CU SEGMENTARE DIAMANT CRESTAT LARGIME D=400MM 1A 1-R 55	BUC.	0.02				0.000
4	6202806 APA INDUSTRIALA PENTRU LUCRARI DRUMURI SI TERASAMENTE IN CISTERNE	M.C.	0.18				0.176
5	6202818 Apa ind.pt.mortare,betoane	M.C.	0.07				0.067
TOTAL					RON		0.798
					EURO		

Ofertant



Lista consumurilor cu mana de lucru (cantitati totale)

Lucrarea: Lucrari de intretinere drum

Devize: SAR119

Nr. Crt.	Denumirea meseriei	Consumuri (om-ore) cu manopera directa	Tarif mediu RON/ora	Valoare(exclusiv TVA) RON (2 x 3)	Procent 100%
0	1	2	3	4	5
1	101 Asfaltator	0.015			
2	102 Betonist	1.928			
3	106 Drenor canalist	2.116			
4	199 Muncitor deserv.c-tii.montaj	7.548			
5	3197 Muncitor inc.-desc.mat.	0.079			
T O T A L		11.686	RON		
			EURO		

Ofertant



Lista consumurilor de ore de functionare a utilajelor de constructii (cantitati totale)

Lucrarea: Lucrari de intretinere drum

Devize: SAR119

Nr. 	Denumirea utilajului de constructii	Consumuri ore de functionare	Tarif orar RON/ ora functionare	Valoare (exclusiv TVA) RON (2 x 3)
0	1	2	3	4
1	1173 BULDOEXCAVATOR CU INCARCATOR	0.285		
2	4058 Masina de taiat rosturi	1.294		
3	5601 Autobasculanta	0.019		
4	5603 Autocisterna	1.300		
T O T A L		2.898	RON	
			EURO	

Ofertant

Formularul F3

Obiectivul: 0013 45000000 TERTI

Obiectul: 0006 538976288 TERTI

Lista cu cantitatile de lucrari

Deviz oferta ROS888 DEMONTAT +MONTAT BORDURA TRAMVAI SCUAR STR BRAILEI

Categoria de lucrari: 8300

Nr. crt.	Capitol de lucr. sau Subcapitol(norma comasata) Denumire	UM	CANTITATEA	PU a)Material b)Manopera c)Utilaj d)Transport (RON /UM)	MATERIAL (col.3x col.4a) (RON)	MANOPERA (col.3x col.4b) (RON)	UTILAJ (col.3x col.4c) (RON)	TRANSPORT (col.3x col.4d) (RON)	TOTAL (col.5+ 6+7+8) (RON)
----------	--	----	------------	---	---	---	---	--	---------------------------------------

Sectiunea tehnica				Sectiunea financiara					
0	1	2	3	4	5	6	7	8	9
001	DG04B1	[1] M	770.000						
	Desfacere borduri din beton								
002	DG06A1	[13] M.C.	34.650						
	Sparg. si desf. beton								
003	TRB05A15	TONA	232.540						
	TRANSPORTUL MATERIALELOR PRIN PURTAT DIRECT.MATERIALE COMODE SUB 25 KG DISTANTA 50M								
004	DA06A1	[11] M.C.	27.720						
	Strat agregate nat. (balast)								
005	DE10A1	[30] M	770.000						
	MONTAT BORDURI 20 x 40 x 50 cm (DE TRAMVAI)								
005	2100969	M.C.	34.650						
	Beton de ciment B 250								
006	TR11AH03E1	[10] TONA	138.010						
	Inc.mat cu buldoexcavatorul								
007	TRA01A10	TONA	138.010						
	Transp.rutier pamant,moloz, mat. cu auto, d=10 km								

008 DF24A1 [2] BUC. 12.000
Semnalizare rutiera lucrari

Cheltuieli directe din articole:

GREUTATE	MATERIALE	MANOPERA	UTILAJ	TRANSPORT	TOTAL
----------	-----------	----------	--------	-----------	-------

Din care:

Valoare aferenta utilaje termice =

Valoare aferenta utilaje electrice =

Detaliere transporturi:

-Articole TRA

Alte cheltuieli directe:

-Contributie asiguratorie pentru munca

Total cheltuieli directe:

GREUTATE	MATERIALE	MANOPERA	UTILAJ	TRANSPORT	TOTAL
----------	-----------	----------	--------	-----------	-------

Cheltuieli indirecte: 0.083

Profit: 0.050

TOTAL GENERAL DEVIZ:

TVA

TOTAL cu TVA

SEF SECTIE IRO
ING. URSACHEL DANIELA

INTOCMIT
ING. SPULBER VIOLETA MICERA

Lista consumurilor de resurse materiale (cantitati totale)

Lucrarea: TERTI

Dezice: ROS888

Nr. Crt.	Denumirea resursei materiale	U.M.	Consumuri cuprinse in oferta	Pret unitar exclusiv TVA RON	Valoare exclusiv TVA RON	Furnizor	Greutate (tone)
0	1	2	3	4	5	6	7
1	2100024 Ciment Portland P 40	KG	2248.40				2.271
2	2100969 Beton de ciment B 250	M.C.	34.65				86.971
3	2200393 Balast nesp.de rau 0-70 mm	M.C.	36.34				61.780
4	2200513 Nisip sort nesp. 0,0-3,0 mm	M.C.	6.16				10.472
5	6202806 APA INDUSTRIALA PENTRU LUCRARI DRUMURI SI TERASAMENTE IN CISTERNE	M.C.	6.43				6.431
6	6202818 Apa ind.pt.mortare,betoane	M.C.	4.62				4.620
7	7640000 BORDURI 20 x 40 x 50 cm (de tramvai)	BUC.	1547.70				136.198
T O T A L					RON		308.743
					EURO		

Ofertant




Lista consumurilor cu mana de lucru (cantitati totale)

Lucrarea: TERTI

Devize: ROS888

Nr. Crt.	Denumirea meseriei	Consumuri (om-ore) cu manopera directa	Tarif mediu RON/ora	Valoare(exclusiv TVA) RON (2 x 3)	Procent 100%
0	1	2	3	4	5
1	128 Pavator	371.625			
2	196 Sapator	108.093			
3	199 Muncitor deserv.c-tii.montaj	1119.757			
TOTAL		1599.475	RON		
			EURO		

Ofertant



Lista consumurilor de ore de functionare a utilajelor de constructii (cantitati totale)

Lucrarea: TERTI

Devize: ROS888

Nr. Crt.	Denumirea utilajului de constructii	Consumuri ore de functionare	Tarif orar RON/ ora functionare	Valoare (exclusiv TVA) RON (2 x 3)
0	1	2	3	4
1	1173 BULDOEXCAVATOR CU INCARCATOR	43.219		
2	4021 Mai mecanic compactor	4.241		
3	5603 Autocisterna	0.638		
TOTAL		48.097	RON	
			EURO	

Ofertant

